



Easiest, Fastest, Install. No Drilling Required. UL Listed and Plenum Rated.



Industry Compliance

CERTIFICATE OF COMPLIANCE

20130912-E359769 Certificate Number E359769-20130912 Report Reference

2013-SEPTEMBER-12 Issue Date

MAG DADDY Issued to:

1155 ROSE RD

LAKE ZURICH, IL, 60047

POSITIONING DEVICES This is to certify that

representative samples of Fixing Devices, designated "Zip Daddy"

Have been investigated by UL in accordance with the

Standard(s) indicated on this Certificate.

UL 62275, Cable Management Systems - Cable Ties for Standard(s) for Safety:

Electrical Installations

Statement from Chicago

"These fasteners are 3rd party tested, and approved for use in the city of Chicago for its product designation"

-Keith Hall (Head of Electrical Inspections Bureau)

PLENUM RATED

"Suitable for use in Air Handling Spaces in accordance with Section 300.22 (C) and (D) of the National Electrical Code and Rules 12-010 (3), (4) and (5) and 12-020 of the Canadian Electrical Code, Part I or an equivalent wording. Alternatively, the abbreviated marking "AH-2" shall be permitted. The word "plenum" shall be allowed in the marking; for example: "...in Air Handling Spaces (plenums)...".

Maximum Operating Temperature: 80°C or 176°F

100 Magnetic Fasteners on 100' Cat. 5E UTP Cable Testing Results

IDEAL INDUSTRIES, Inc. Certified - Test Report

Job Name: 100FT.job Company: COMPANY NAME

Test Name: -5 Test Limit: Cat 5E UTP Perm

User Notes:

LANTEK II-350 [1146437/1146447] dapter ID: 6000, Cat 6 Chan

Pass

NVP: 72 Standard: TIA 568-B.2 Frequency Range: 1 - 100MHz Firmware 2.012 Report Date: Friday, October 19, 2012 9:36 AM Version: 1.3.1

> Test Date: 10/18/2012 Test Time: 10:03:20 Operator: OPERATOR NAME Contractor: CONTRACTOR NAME Company: COMPANY NAME

-Deemed Data safe with Passing Grade in worst case scenario testing



